STANDARD NOTES FOR CONTRACTOR INSTALLED SIGNING AND STRIPING

("X")

INSTALL "X" STRIPING

MAINTAIN AND PROTECT EXISTING "X" STRIPING

REMOVE EXISTING "X" STRIPING

<u>"x"</u> STRIPING NOTES EDGE LINE E-2WIDE EDGE LINE

W-2PLASTIC WHITE 4-IN LINE

PLASTIC WHITE 8-IN LINE W-3

WIDE LINE

WB LANE LINE

WD WIDE DOTTED LINE

DF DOTTED EXTENSION LINE

WDE WIDE DOTTED EXTENSION LINE

DLL DROP LANE LINE

PAINT YELLOW 4-IN LINE

Y-2 PLASTIC YELLOW 4-IN LINE

YΒ SKIP CENTERLINE

DOUBLE YELLOW CENTERLINE

NO-PASS LINE

TWL TWO-WAY LEFT TURN LINE BBL

BUFFERED BIKE LANE

CW CROSSWALK STOP LINE

LA LEFT TURN ARROW

RA RIGHT TURN ARROW

LSA LEFT TURN STRAIGHT ARROW

RSA RIGHT TURN STRAIGHT ARROW

RSLA RIGHT TURN STRAIGHT LEFT ARROW

RALA RIGHT TURN LEFT TURN ARROW

SA STRAIGHT ARROW

LRA LANE REDUCTION ARROW

WWA WRONG WAY ARROW

BS BICYCLE LANE SYMBOL

BR BIKE RIDER SYMBOL

SH SHARED LANE "SHARROW" SYMBOL

RR RAII ROAD CROSSING SYMBOL

YLD YIELD LINE SYMBOL

YTMYELLOW TUBULAR MARKER

WHITE TUBULAR MARKER WTM

ON "ONLY"

СН CROSSHATCH MARKING

SIGNING NOTES

PROTECT EXISTING POST

SIGN CODE (# NEW SIGN ASSEMBLY

SIGN CODE SIGN CODE

SIGN CODE RS SIGN CODE RP PROTECT EXISTING SIGN ASSEMBLY REMOVE EXISTING SIGN ASSEMBLY REMOVE AND SAVE EXISTING SIGN ASSEMBLY REMOVE EXISTING SIGN ASSEMBLY AND

(NEW LOCATION) SIGN CODE # < RELOCATE EXISTING SIGN ASSEMBLY

(EXISTING LOCATION)

GENERAL NOTES.

- THE SIGNING, STRIPING, PAVEMENT MARKINGS AND OTHER TRAFFIC CONTROL DEVICES SHALL BE CONTIGUOUS WITH THE EXISTING TRAFFIC CONTROL AND TRAFFIC OPERATIONS.
- 2. THE CONTRACTOR SHALL MAINTAIN EXISTING PERMANENT SIGNING, STRIPING, PAVEMENT MARKINGS AND TUBULAR MARKERS IN ACCORDANCE WITH SECTION 1-07.23(1)
- 3. ANY LOOPS DAMAGED OR DESTROYED DURING WORK PERFORMED IN COUNTY RIGHT-OF-WAY SHALL BE REPLACED IN ACCORDANCE WITH CCC 12.20A. SPLICES WILL

STRIPING AND PAVEMENT MARKING NOTES:

- ALL NEW STRIPING, PAVEMENT MARKINGS, TUBULAR MARKERS, SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR.
- 2. THE CONTRACTOR SHALL REMOVE STRIPING AND PAVEMENT MARKINGS AS SHOWN IN THE CONTRACT PLANS OR AS DIRECTED BY THE ENGINEER. THE STRIPING AND PAVEMENT MARKING REMOVAL PROCESS SHALL CONFORM TO SECTION 8-22.3(6) OF WSDOT STANDARD SPECIFICATIONS.
- 3. ALL PAVEMENT MARKINGS WILL BE LAID OUT IN THE FIELD BY THE ENGINEER.
- PAVEMENT MARKING SYMBOLS MUST BE TYPE B PRE-FORMED FUSED THERMOPLASTIC PER 9-34.3(2) OF WSDOT STANDARD SPECIFICATIONS UNLESS OTHERWISE SPECIFIED. SEE CLARK COUNTY SPECIAL PROVISIONS FOR INSTALLATION DETAILS.
- SEE CLARK COUNTY SPECIAL PROVISIONS FOR DETAILS REGARDING GREEN PAVEMENT
- THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY PAVEMENT MARKINGS IN ACCORDANCE WITH SECTION 8-23 OF THE SPECIFICATIONS.

SIGNING NOTES

- 1. ALL NEW SIGNING SHALL BE PROVIDED AND INSTALLED BY THE CONTRACTOR.
- THE CONTRACTOR SHALL REMOVE SIGNS AS SHOWN IN THE CONTRACT PLANS OR AS DIRECTED BY THE ENGINEER
- 3. ALL SIGNS WILL BE FIELD STAKED BY THE ENGINEER.
- 4. R1-1 SIGNS SHALL BE TYPE XI SHEETING MATERIAL WITH PROTECTIVE OVERLAY FILM.
- ALL SIGNS INSTALLED ON TRAFFIC SIGNAL POLES AND MASTARMS SHALL BE TYPE IX SHEETING MATERIAL.
- 6. FLUORESCENT YELLOW GREEN SIGNS SHALL BE TYPE IX SHEETING MATERIAL.
- SIGNS INSTALLED ON TRAFFIC SIGNAL AND LIGHT STANDARDS SHALL BE INSTALLED PER WSDOT STANDARD PLAN G-30.10-04.
- THE CONTRACTOR SHALL SURPLUS ALL SIGNS (EXCEPT BARRICADES) AND POSTS TO CLARK COUNTY PUBLIC WORKS AT NO COST TO THE CONTRACT. THE SIGNS AND POSTS SHALL BE RETURNED TO THE COUNTY 149TH STREET MAINTENANCE STATION, LOCATED AT 11608-B NE 149TH STREET, BRUSH PRAIRIE, WA, 98606, AND CONTACTED AT (564) 397-2348.
- 9. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN CONSTRUCTION SIGNS IN ACCORDANCE WITH SECTION 1-10 OF THE SPECIFICATIONS.

	REV. NO.	DATE	BY	APPR
				STANDARD
STANDARD NOTES FOR CONTI	RACTOR	INSTALL	$_{\prime}ED$	

SIGNING AND STRIPING

APPROVED 07/17/19 ORAWN

DETAIL

SIGNED

Department of Public Works **CLARK COUNTY** WASHINGTON proud past, promising future