N.E. 152ND AVENUE (NE Padden Parkway to NE 99th Street) PRJ0000586/CRP301022


Virtual Open House

Troy Pierce, P.E., Project Manager

June 29, 2022, 5:00 – 6:00 pm




Using WebEx on a browser (Chrome, Safari, etc.)





Using the desktop app





On a mobile device app

During a meeting, go to the people list



, and then tap Raise Hand.

A raised hand



appears beside your name in the people list, indicating to the host that you want to speak.

If the host allows you to speak, you're prompted to unmute yourself.

To lower your hand, go to the people list



, and then tap Lower Hand.



Project Goals

Enhance:

- Safety for all modes of transportation, especially at intersections and York Elementary School;
- Infrastructure conditions to meet current standards;
- Multi-modal access along the corridor and at the intersections;
- System reliability, transit access and freight movement;
- Network connectivity with this north/south connection between Padden Parkway/SR 500 and NE 99th Street







Project Overview

- Roadway classification: C-2b
 - Collector arterial
 - 2 travel lanes
 - · Bike facilities
- Center left-turn lane only for southbound traffic at school's north entrance
- Pedestrian crossing north of school's south entrance
- New traffic signal at NE 99th Street and NE 152nd Avenue
 - Left-turn lane on each leg
 - Roundabout considered but discarded





NE 152ND AVENUE NE PADDEN PARKWAY TO NE 99TH STREET

Project Funding

Funding sources

- Federal Funds STPUL
 - Surface Transportation Program Urban Block Grant
- State Funds TIB
 - Transportation Improvement Board
 - Seeking funds; application in August
- Local Funds
 - Traffic Impact Fees
 - County Road Fund





Project Costs


- Estimated Project Costs \$9,100,000
- 3 Phases
 - Preliminary Engineering
 - Engineering roadway, stormwater, geotechnical, traffic
 - Environmental Documentation and permitting
 - Right-of-Way
 - Acquisition
 - Construction
 - Construction Contract
 - Construction Management





Preliminary Engineering

- Roadway
 - Generally flat; very little change in the "vertical profile" of the roadway (rise and fall)
 - Keeping curb, gutter and sidewalk in some locations
 - Evaluating crown and slope of existing road against proposed crown




NE 152nd Ave Proposed Roadway Section




Preliminary Engineering

- Stormwater
 - All infiltration; no runoff to streams
 - Runoff treated (cleaned) in catch basin filters
 - Runoff infiltrated in trench in roadway









Preliminary Engineering

- Geotechnical
 - Geotechnical Report- Study of existing soil conditions to determine how well it will infiltrate (drain)
 - Pavement Report- Study of existing pavement conditions and recommended improvements

Coefficient of Boring Test Depth, feet Soil Type Fines Content, % Silty SAND, some B-3 4 feet 12 4 gravel Gravelly SAND, B-5 4 feet 11 Sandy GRAVEL, B-7 4 feet 11 some silt Sandy GRAVEL,

some silt

Table 5-1: SUMMARY OF INFILTRATION TEST RESULTS



10

| Station | | | |
|-----------|--------|----------------|--------------|
| Beginning | Ending | Treatment | Length, feet |
| 14+60 | 18+40 | Rehabilitation | 380 |
| 18+40 | 19+50 | Reconstruction | 110 |
| 19+50 | 20+75 | Rehabilitation | 125 |
| 20+75 | 23+35 | Reconstruction | 260 |
| 23+35 | 25+30 | Rehabilitation | 195 |
| 25+30 | 26+35 | Reconstruction | 105 |
| 26+35 | 31+30 | Rehabilitation | 495 |
| 31+30 | 35+15 | Reconstruction | 385 |
| 35+15 | 35+60 | Rehabilitation | 45 |
| 35+60 | 36+25 | Reconstruction | 65 |
| 36+25 | 37+20 | Rehabilitation | 95 |
| 37+20 | 39+20 | Reconstruction | 200 |
| 39+20 | 43+15 | Rehabilitation | 395 |
| 43+15 | 43+65 | Reconstruction | 50 |
| 43+65 | 44+20 | Rehabilitation | 55 |
| 44+20 | 45+20 | Reconstruction | 100 |
| 45+20 | 48+45 | Rehabilitation | 325 |
| 48+45 | 49+25 | Reconstruction | 80 |
| 49+25 | 53+25 | Rehabilitation | 400 |
| 53+25 | 54+20 | Reconstruction | 95 |
| 54+20 | 56+15 | Rehabilitation | 195 |
| 56+15 | 59+50 | Reconstruction | 335 |
| | Total | Rehabilitation | 2,705 |
| | Total | Reconstruction | 1.785 |

Note: Station 10+00 = Centerline of NE 102nd Way



RECONSTRUCTION AREA
REHABILITATION AREA



DRAFT




B-8

4 feet

Preliminary Engineering

- Traffic
 - Signing
 - Striping
 - Left-turn lane
 - Pedestrian crossing
 - Traffic signal







Preliminary Engineering

- Environmental
 - Documentation/Permitting
 - Cultural Resources
 - · Historic Resources
 - Archaeological Survey
 - NEPA National Environmental Protection Act
 - Endangered Species Act (ESA)
 - SEPA State Environmental Protection Act
 - Critical Areas
 - · Wetland Protection
 - Habitat Conservation






Preliminary Engineering

- Environmental
 - · Documentation/Permitting
 - Cultural Resources
 - Historic Resources
 - Archaeological Survey


Pedestrian Archaeology Survey

- Adjacent areas with open spaces or without constructed frontage most likely to be selected
- · Shovel test pits completed
 - 20 in. diam at surface
 - 20 in. minimum depth
- Excavated soil screened and replaced and any findings logged



Right-of-Way


- Right-of-way plans
 - Prepared to reflect impact of project
 - Completed between 65% and 90%
- Appraisals
- Offers
- Acceptance
- Payment





Construction

- Currently intended to be constructed under traffic
 - Long-term detour with road closure not currently proposed
 - May reconsider as design advances (access, school)
 - Possible temporary detours with flaggers
 - Likely temporary closures (20 minutes) with flaggers





16

Construction

- Staging
 - Open areas needed for construction contractor's equipment and materials
 - Difficult to find places along developed roads
 - County hopes to permit several potential options
 - County hopes to permit several potential options
 - But ultimately up to property owner and contractor (3rd Party Agreement)
 - Interest?







Project Schedule (Tentative)

- Open house Jun 29, 2022
- Permit Plans Aug 19, 2022
 - Cultural Resource Investigation Letters
- 90% Plans Dec 16, 2022
 - Right-of-way plans
- Right-of-way acquisition Mar 2023–Mar 2024
- Potential second open house Apr 2024
- Bid Opening Oct 2024
- Construction Apr 2025–Oct 2025



Project Questions

Addresses

- Administrative error that mixed names and parcel numbers with addresses
- Does not affect parcel data in county system (e.g., for taxing purposes)





Project Questions

- Cut-through traffic on NE 150th Avenue
- Safety measures for pedestrians at York Elementary school crosswalk
 - Can a flashing light crosswalk be installed?





Contact Information

Project Manager

- Troy Pierce, P.E.
- troy.pierce@clark.wa.gov
- 564-397-4403

General Communications

• pw.outreach@clark.wa.gov



21

Thank you!

Comments and questions


Clark County Public Service Center

1300 Franklin Street • PO Box 5000

Vancouver, WA 98666-5000




Using WebEx on a browser (Chrome, Safari, etc.)





Using the desktop app





On a mobile device app

During a meeting, go to the people list



, and then tap Raise Hand.

A raised hand



appears beside your name in the people list, indicating to the host that you want to speak.

If the host allows you to speak, you're prompted to unmute yourself.

To lower your hand, go to the people list



, and then tap Lower Hand.

